SMA READYRACKTM





Turnkey

- Delivered with fully integrated Sunny Tripower inverter, DC Connection Unit, and AC disconnect switch
- Complete ground bonding of all components

Speeds installation

- Pre-installed EPDM foot pads for direct placement on roof
- Reduces field wiring time and labor

Code compliant

- Fulfills NEC 690.12 Rapid Shutdown requirement
- Inverter integrated DC AFCI
 protection

Durable

- Corrosion resistant aluminum rack structure
- Stainless steel mounting hardware

SMA READYRACKTM

The time-saving commercial rooftop solution

The SMA ReadyRack™ is specifically designed for the world's top-selling three-phase inverter, the Sunny Tripower TL-US. The SMA ReadyRack allows for a simplified installation that includes all balance of system components, such as the AC disconnect, combiners, cables and more. As its name states, the ReadyRack can be installed within minutes on flat commercial rooftops. It's ideally designed for mounting within 10-feet of the PV array to comply with the NEC 690.12 rapid shutdown requirements. Experience a simpler, faster commercial install with the ReadyRack.

Technical data

General data

Rack mount materials Weight (with installed equipment) Shipping weight Height (in operating position with installed equipment) Width Length (in operating position) Shipping dimensions (in inches) AC disconnect DC connection unit Compatible inverters (depends on ReadyRack variant) Warranty

General information

Variants

Rack-STP12-CU-11 Rack-STP15-CU-11 Rack-STP20-CU-11 Rack-STP24-CU-11 Rack-STP30-CU-11

Aluminium rack structure, stainless steel hardware, EPDM foot pads 180 lbs Pending 27 in 26.5 in 53 in 63"(L) × 34" (W) × 76" (H) 60A, non-fusible, UL 508 SMA CU 1000-US Sunny Tripower 12000TL-US/15000TL-US/24000TL-US/30000TL-US 5 years parts and workmanship (inverter and CU 1000-US warrantied separately) Inverter and SMA CU 1000-US priced and sold separately. Integrated rack includes mounted

ReadyRack for STP 12000TL-US inverter ReadyRack for STP 15000TL-US inverter ReadyRack for STP 20000TL-US inverter ReadyRack for STP 24000TL-US inverter ReadyRack for STP 30000TL-US inverter

and pre-wired inverter, SMA CU 1000-US, and AC disconnect. Rack not sold separately.

Type designation

Rack-STP12-CU-11 / Rack-STP15-CU-11 / Rack-STP20-CU-11 / Rack-STP24-CU-11 / Rack-STP30-CU-11

Toll Free +1 888 4 SMA USA www.SMA-America.com SMA READYRACK