



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)  
BOARD AND CODE ADMINISTRATION DIVISION

**NOTICE OF ACCEPTANCE (NOA)**

MIAMI-DADE COUNTY  
PRODUCT CONTROL SECTION  
11805 SW 26 Street, Room 208  
Miami, Florida 33175-2474  
T (786) 315-2590 F (786) 315-2599  
[www.miamidade.gov/economy](http://www.miamidade.gov/economy)

**K2 Systems, LLC**  
**4665 North Ave. Suite 1**  
**Oceanside, CA 92056**

**SCOPE:** This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER-Product Control Section to be used in Miami-Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

**DESCRIPTION: Splice Foot X, Splice Foot XL and L-Foot Ecofasten w/ eComp Flashing Aluminum Solar Mounts**

**APPROVAL DOCUMENT:** Drawing titled "Splice Foot X, Splice Foot XL and Everflash eComp Kit", sheets 1 through 12 of 12, prepared by K2 Systems, dated on 01/11/2022, with revision C dated 07/07/2022, signed and sealed by Paul K. Zacher, P.E., bearing the Miami-Dade County Product Control revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

**MISSILE IMPACT RATING: None**

**LABELING:** Each box shall bear a permanent label with the manufacturer's name or logo, city, state and following statement: "Miami-Dade County Product Control Approved or MDCPCA", unless otherwise noted herein.

**Limitation: The allowable fastener uplift and lateral on drawing sheets 3 and 6 are total (for the 2 fasteners).**

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA **revises NOA # 22-0516.04** and consists of this page 1, evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by **Carlos M. Utrera, P.E.**



**NOA No: 22-0719.06**  
**Expiration Date: February 17, 2027**  
**Approval Date: August 25, 2022**  
**Page 1**

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**1. Evidence submitted under previous NOAs**

**A. DRAWINGS**

1. Drawing titled “Splice Foot X and Everflash eComp Kit”, sheets 1 through 9 of 9, prepared by K2 Systems, dated on 01/11/2022, signed and sealed by Paul K. Zacher, P.E. on 05/09/2022.

**B. TESTS “Submitted under NOA # 21-0727.03”**

1. Test report on Uplift and Shear Allowable Loads of the eComp Flashing Solar Mount per ASTM D7147-11, prepared by Intertek, Test Report No. **M1451.02-119-18 R0**, dated 06/29/2021, signed and sealed by Daniel C. Culbert, P.E.
2. Test report on Uplift and Shear Allowable Loads of the Splice Foot per ASTM D7147-11, prepared by Intertek, Test Report No. **M1453.02-119-18 R0**, dated 06/29/2021, signed and sealed by Daniel C. Culbert, P.E.
3. Test report on Wind Driven Rain Resistance of the eComp Flashing per TAS 100(A)-95, prepared by Intertek, Test Report No. **M1451.01-109-18**, dated 05/18/2021, signed and sealed by Daniel C. Culbert, P.E.
4. Test report on Wind Driven Rain Resistance of the Splice Foot per TAS 100(A)-95, prepared by Intertek, Test Report No. **M1453.01-109-18**, dated 05/18/2021, signed and sealed by Daniel C. Culbert, P.E.

**C. CALCULATIONS “Submitted under NOA # 21-0727.03”**

1. Anchor calculations prepared by PZ Structural Engineers, dated 01/24/2022, signed and sealed by Paul K. Zacher, P.E.

**D. MATERIAL CERTIFICATIONS**

1. None.

**E. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER).

**F. STATEMENTS “Submitted under NOA # 21-0727.03”**

1. Statement letter of code conformance to the 7<sup>th</sup> edition (2020) of the FBC issued by PZ Structural Engineers, dated 01/24/2022, signed and sealed by Paul K. Zacher, P.E.
2. Statement letter of no financial interest issued by PZ Structural Engineers, dated 07/13/2021, signed and sealed by Paul K. Zacher, P.E.



---

**Carlos M. Utrera, P.E.**  
**Product Control Examiner**  
**NOA No: 22-0719.06**  
**Expiration Date: February 17, 2027**  
**Approval Date: August 25, 2022**

**NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED**

**2. New evidence submitted**

**A. DRAWINGS**

1. Drawing titled “Splice Foot X, Splice Foot XL and Everflash eComp Kit”, sheets 1 through 12 of 12, prepared by K2 Systems, dated on 01/11/2022, with revision C dated 07/07/2022, signed and sealed by Paul K. Zacher, P.E.

**B. TESTS**

1. Test report on Uplift and Shear Allowable Loads of the Splice Foot XL Solar Mount per ASTM D7147-11, prepared by Intertek, Test Report No. **N8734.01-119-18-R0**, dated 06/29/2022, signed and sealed by Vinu J. Abraham, P.E.
3. Test report on Wind Driven Rain Resistance of the Splice Foot XL Solar Mount per TAS 100(A)-95, prepared by Intertek, Test Report No. **N2321.01-109-18**, dated 02/23/2022, signed and sealed by Vinu J. Abraham, P.E.

**C. CALCULATIONS**

1. Anchor calculations prepared by PZ Structural Engineers, dated 07/11/2022, signed and sealed by Paul K. Zacher, P.E.

**D. MATERIAL CERTIFICATIONS**

1. None.

**E. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER).


**F. STATEMENTS**

1. Statement letter of code conformance to the 7<sup>th</sup> edition (2020) of the FBC issued by PZ Structural Engineers, dated 07/11/2022, signed and sealed by Paul K. Zacher, P.E.
2. Statement letter of no financial interest issued by PZ Structural Engineers, dated 07/11/2022, signed and sealed by Paul K. Zacher, P.E.




---


**Carlos M. Utrera, P.E.**  
**Product Control Examiner**  
**NOA No: 22-0719.06**  
**Expiration Date: February 17, 2027**  
**Approval Date: August 25, 2022**



PART BILL OF MATERIALS				
ITEM	QTY	DESCRIPTION	ALLOY MATERIAL	TEMPER
1	1	SPLICE FOOT X	AL 6005A	T61
2	1	SPLICE FOOT BUTYL, 3 1/2"X4"	N/A	N/A
3	2	K2 WOOD SCREW MINI	STAINLESS STEEL	N/A
4	2	SEALING WASHER	SS AND EPDM	N/A
5	1	T-BOLT 28/15 M10X25 SS	STAINLESS STEEL	N/A
6	1	HEX FLANGE NUT SERR, SS, M10	STAINLESS STEEL	N/A



SPLICE FOOT X DIMENSIONS



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *R. Estrada*  
 Miami-Dade Product Control

**K2 Systems**  
 4665 North Avenue Suite 1  
 Oceanside, CA 92056  
 phone 760.301.5300

DESCRIPTION:  
 SPLICE FOOT X KIT ASSEMBLY





REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	

DRAWN BY  
 R. ESTRADA

Project:  
 Miami Dade County NOA

SCREW MATERIAL: STAINLESS STEEL 304

PART BILL OF MATERIALS			
ITEM	QTY	DESCRIPTION	MATERIAL
1	1	K2 WOOD SCREW MINI	STAINLESS STEEL
2	1	SEALING WASHER	STAINLESS STEEL AND EPDM



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *[Signature]*  
 Miami-Dade Product Control

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	

**K2 Systems**  
 4665 North Avenue Suite I  
 Oceanside, CA 92056  
 phone 760.301.5300

DESCRIPTION: K2 WOOD SCREW MINI DETAIL

DRAWN BY: R. ESTRADA

Project: Miami Dade County NOA



**SPLICE FOOT X FOR COMPOSITION SHINGLE ROOF MOUNTING**

REFER TO K2 ENGINEERING CHARTS FOR APPLCABLE CROSSRAIL SPANS

FOR USE AS A RAIL SPLICE, DISTANCE TO THE NEXT SPLICE FOOT X MOUNT MUST BE EQUAL OR LESS THAN THE MAX ALLOWABLE ATTACHMENT SPAN PER K2 ENGINEERING CHARTS

NO PILOT HOLE REQUIRED FOR SELF DRILLING SCREWS

REFER TO K2 CROSSRAIL INSTLATION MANUAL FOR HARDWARE TORQUE

**STRUCTURAL MEMBER SPECIFICATIONS:**

MINIMUM WOOD GRADE = SPF #2




MINIMUM SPECIFIC GRAVITY = 0.42

ALLOWABLE FASTENER UPLIFT = 507.7 LBS

ALLOWABLE FASTENER LATERAL = 216 LBS


MINIMUM FASTENER EDGE DISTANCE = 0.3"

MINIMUM FASTENER END DISTANCE = 1.4"



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida  
 Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *[Signature]*  
 Miami-Dade Product Control





DESCRIPTION:  
 SPLICE FOOT X ATTACHMENT DETAIL

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	

DRAWN BY: R. ESTRADA  
 Project: Miami Dade County NOA


REIURED TOOLS:  
 5/16" SOCKET  
 SOCKET WRENCH  
 COMP SHINGLE START COURSE OR K2 BUTYL (FOR UNEVEN SURFACES)



STEP 1:  
 Corner out and mark array on roof.  
 Snap chalk lines for rail location within  
 shingle course. (Refer to module manufacturer  
 frame clamping zones). Mark mounting  
 locations over rafters and chalk lines within  
 shingle course. Refer to engineering letters for  
 allowable mount spacing.

STEP 1 (CONTINUED):  
**LEVELING UNEVEN ROOF SURFACES:**  
 If shingle surface is not level, use an additional  
 piece of K2 butyl or a standard comp  
 shingle starter course to level out the roof  
 surface under the Splice Foot.

STEP 2:  
 Locate the rafter and clean roofing surface for mount placement.  
 Peel back protective paper from butyl, and stick down mount on a  
 single shingle course with the two center holes lining up over the rafter.  
 Position all mounts in the same direction with the long side towards  
 the ridge. Drive provided lag screws into the rafter until the EPDM seal  
 begins to deform, providing a positive seal. Do not over torque.



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida  
 Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *[Signature]*  
 Miami-Dade Product Control


**K2** Systems  
 4665 North Avenue Suite I  
 Oceanside, CA 92056  
 phone 760.301.5300

DESCRIPTION:  
 SPLICE FOOT X INSTALLATION

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	


DRAWN BY  
 R. ESTRADA

Project:  
 Miami Dade County NOA




PART BILL OF MATERIALS				
ITEM	QTY	DESCRIPTION	ALLOY MATERIAL	TEMPER
1	1	SPLICE FOOT XL	AL 6005A	T61
2	1	SPLICE FOOT BUTYL, 3 1/2"X4"	N/A	N/A
3	2	K2 WOOD SCREW MINI	STAINLESS STEEL	N/A
4	2	SEALING WASHER	SS AND EPDM	N/A
5	1	T-BOLT 28/15 M10X25 SS	STAINLESS STEEL	N/A
6	1	HEX FLANGE NUT SERR, SS, M10	STAINLESS STEEL	N/A

EXPLODED ASSEMBLY



SPLICE FOOT XL DIMENSIONS



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *[Signature]*  
 Miami-Dade Product Control

**K2 Systems**  
 4665 North Avenue Suite I  
 Oceanside, CA 92056  
 phone 760.301.5300

DESCRIPTION:  
 SPLICE FOOT XL KIT ASSEMBLY

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	

DRAWN BY  
 R. ESTRADA

Project:  
 Miami Dade County NOA



**SPLICE FOOT XL FOR COMPOSITION SHINGLE ROOF MOUNTING**

REFER TO K2 ENGINEERING CHARTS FOR APPLCABLE CROSSRAIL SPANS

FOR USE AS A RAIL SPLICE, DISTANCE TO THE NEXT SPLICE FOOT XL MOUNT MUST BE EQUAL OR LESS THAN THE MAX ALLOWABLE ATTACHMENT SPAN PER K2 ENGINEERING CHARTS

NO PILOT HOLE REQUIRED FOR SELF DRILLING SCREWS




REFER TO K2 CROSSRAIL INSTLATION MANUAL FOR HARDWARE TORQUE

**STRUCTURAL MEMBER SPECIFICATIONS:**

MINIMUM WOOD GRADE = SPF #2  
MINIMUM SPECIFIC GRAVITY = 0.42

ALLOWABLE FASTENER UPLIFT = 424 LBS  
ALLOWABLE FASTENER LATERAL = 216 LBS

MINIMUM FASTENER EDGE DISTANCE = 0.295"  
MINIMUM FASTENER END DISTANCE = 1.4"



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
as complying with the Florida Building Code  
NOA-No. 22-0719.06  
Expiration Date 02/17/2027  
By *R. Estrada*  
Miami-Dade Product Control

**K2 Systems**  
4665 North Avenue Suite  
Oceanside, CA 92056  
phone 760.301.5300



DESCRIPTION:  
SPLICE FOOT XL ATTACHMENT DETAIL

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	

DRAWN BY  
R. ESTRADA

Project:  
Miami Dade County NOA


REUIRED TOOLS:  
 5/16" SOCKET  
 SOCKET WRENCH  
 COMP SHINGLE START COURSE OR K2 BUTYL (FOR UNEVEN SURFACES)



STEP 1:  
 Corner out and mark array on roof.  
 Snap chalk lines for rail location within  
 shingle course. (Refer to module manufacturer  
 frame clamping zones). Mark mounting  
 locations over rafters and chalk lines within  
 shingle course. Refer to engineering letters for  
 allowable mount spacing.


STEP 1 (CONTINUED):  
 LEVELING UNEVEN ROOF SURFACES:  
 If shingle surface is not level, use an additional  
 piece of K2 butyl or a standard comp  
 shingle starter course to level out the roof  
 surface under the Splice Foot.

STEP 2:  
 Locate the rafter and clean roofing surface for mount placement.  
 Peel back protective paper from butyl, and stick down mount on a  
 single shingle course with the two center holes lining up over the rafter.  
 Position all mounts in the same direction with the long side towards  
 the ridge. Drive provided lag screws into the rafter until the EPDM seal  
 begins to deform, providing a positive seal. Do not over torque.



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida  
 Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *R. Estrada*  
 Miami-Dade Product Control




DESCRIPTION:  
 SPLICE FOOT XL INSTALLATION

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	


DRAWN BY  
 R. ESTRADA

Project:  
 Miami Dade County NOA



ECOFASTEN COMP FLASHING 8X12


SCALE 1:4




COMPLETE ASSEMBLY

PART BILL OF MATERIALS			
ITEM	QTY	DESCRIPTION	ALLOY MATERIAL
1	1	K2 L-FOOT ECOFASTEN	AL 6005A
2	1	ECOFASTEN COMP FLASHING 8X12	GALVALUME
3	1	ECOFASTEN SEALING WASHER	EPDM
4	1	LAG SCREW D145/16 X 4.5"	STAINLESS STEEL
5	1	LAG SCREW SEALING WASHER	SS AND EPDM
6	1	T-BOLT 28/15 M10X25 SS	STAINLESS STEEL
7	1	HEX FLANGE NUT SERR, SS, M10	STAINLESS STEEL

2X R.22




K2 L-FOOT ECOFASTEN DIMENSIONS



EXPLODED ASSEMBLY

**PRODUCT REVISED**  
 as complying with the Florida  
 Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *[Signature]*  
 Miami-Dade Product Control



PE SIGNATURE:

PE DATE:

07/11/2022



K2 Systems  
 4665 North Avenue Suite I  
 Oceanside, CA 92056  
 phone 760.301.5300

DESCRIPTION:

EVERFLASH ECOMP KIT 4.5" LAG ASSEMBLY

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	

DRAWN BY





R. ESTRADA

Project:

Miami Dade County NOA

LAG SCREW MATERIAL: 18-8 STAINLESS STEEL

PART BILL OF MATERIALS			
ITEM	QTY	DESCRIPTION	ALLOY MATERIAL
1	1	LAG SCREW D145/16 X 4.5"	STAINLESS STEEL
2	1	LAG SCREW SEALING WASHER	SS AND EPDM



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida  
 Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *[Signature]*  
 Miami-Dade Product Control

DESCRIPTION:  
 ECOMP LAG SCREW D145/16 X 4.5" DETAIL

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	

DRAWN BY  
 R. ESTRADA

Project:  
 Miami Dade County NOA






EVERFLASH ECOMP KIT FOR COMPOSITION SHINGLE ROOF MOUNTING  
 REFER TO K2 ENGINEERING CHARTS FOR APPLCABLE CROSSRAIL SPANS  
 DRILL 1/4" PILOT HOLE FOR LAG BOLT  
 REFER TO K2 CROSSRAIL INSTALLATION MANUAL FOR HARDWARE TORQUE

**STRUCTURAL MEMBER SPECIFICATIONS:**  
 MINIMUM WOOD GRADE = SPF #2  
 MINIMUM SPECIFIC GRAVITY = 0.42

ALLOWABLE FASTENER UPLIFT = 906.7 LBS  
 ALLOWABLE FASTENER LATERAL = 250 LBS

MINIMUM FASTENER EDGE DISTANCE = 0.5"  
 MINIMUM FASTENER END DISTANCE = 2.2"



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *R. Estrada*  
 Miami-Dade Product Control

**K2 Systems**  
 4665 North Avenue Suite I  
 Oceanside, CA 92056  
 phone 760.301.5300

DESCRIPTION:  
 EVERFLASH ECOMP KIT ATTACHMENT DETAIL

REVISION	DATE	DESCRIPTION	DRAWN BY
A	01/11/2022	INITIAL RELEASE	R. ESTRADA
B	05/10/2022		
C	07/07/2022		


Project: Miami Dade County NOA




REQUIRED TOOLS:  
 CHALK LINE  
 ROOFING BAR  
 1/4" DRILL BIT  
 ROOFING MANUFACTURER APPROVED SEALANT

STEP 1:  
 Locate rafters and snap horizontal and vertical lines to mark the installation position for each EVERFLASH ECOMP

STEP 2:  
 It is important to remove any obstructing nails in the 2nd course of shingles as they can prevent the flashing from extending up under the 3rd course of shingles.  
 This is required by the roofing manufacturer's instructions and warranties, and the Asphalt Roofing Manufacturer's Association guidelines.  
 Use roofing bar to break the seals between the 1st and 2nd, and 2nd and 3rd shingle courses. Be sure to remove all nails to allow correct placement of flashing.



STEP 3:  
 Drill pilot hole and fill with roofing manufacturer approved sealant.



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
 as complying with the Florida Building Code  
 NOA-No. 22-0719.06  
 Expiration Date 02/17/2027  
 By *R. Estrada*  
 Miami-Dade Product Control

DESCRIPTION:  
 EVERFLASH ECOMP KIT INSTALLATION

REVISION	DATE	DESCRIPTION
A	01/11/2022	INITIAL RELEASE
B	05/10/2022	
C	07/07/2022	


DRAWN BY  
 R. ESTRADA

Project:  
 Miami Dade County NOA


**K2 SYSTEMS**  
 K2 Systems  
 4665 North Avenue Suite I  
 Oceanside, CA 92056  
 phone 760.301.5300

REQUIRED TOOLS:


13MM DEEP SOCKET  
SOCKET WRENCH



STEP 4:  
Slide the eComp flashing under the 2nd course of shingles so that the bottom flashing edge does not overhang the butt edge of the shingles. This requirement ensures that the flashing extends up under the 3rd course of shingles and the minimum head-lap is achieved.



STEP 4:  
Line up pilot hole with the flashing hole. Insert the lag screw through EPDM bonded washer, L-Foot, gasketed hole in flashing and into rafter. The torque range is between 8.3 - 11.6 ft-lbs depending on type of wood and time of year.



PE SIGNATURE: \_\_\_\_\_ PE DATE: 07/11/2022

**PRODUCT REVISED**  
as complying with the Florida  
Building Code  
NOA-No. 22-0719.06  
Expiration Date 02/17/2027  
By *R. Estrada*  
Miami-Dade Product Control



K2 Systems  
4665 North Avenue Suite I  
Oceanside, CA 92056  
phone 760.301.5300

DESCRIPTION:  
EVERFLASH ECOMP KIT INSTALLATION

REVISION	DATE	DESCRIPTION	DRAWN BY
A	01/11/2022	INITIAL RELEASE	R. ESTRADA
B	05/10/2022		
C	07/07/2022		

Project:  
Miami Dade County NOA